BILL OF QUANTITIES

ICF KIT · CONCRETE · LABOUR

REDCATCH QUARTER, KNOWLE, BRISTOL

91 Three-Storey Terraced Houses · 7 blocks · Redcatch Road, Knowle, Bristol · ENGLAND

Quotation Reference	ES26-064
Project	Redcatch Quarter, Knowle, Bristol
House Type	3B5P three-storey terraced house, 4,080 x 10,312 (one type, 91 plots): 6in XR35 external walls incl. the FB course, 6in Standard party walls, rear 2F balcony behind a 1,500 set-back, ICF gables at the block ends, stepped blocks
Client	Cuckfield Real Estate Ltd
Site Address	Redcatch Quarter, Redcatch Road, Knowle, Bristol BS4
BOQ Date	10 November 2026
BOQ Reference	BOQ-ES26-064
Prepared by	Tom Smith — BuildEase Manager, Nudura UK
Issued by	Tremco Construction Products Group
Currency	Pound Sterling (GBP) · VAT at 20%
Measurement Convention	RICS New Rules of Measurement (NRM2)

IMPORTANT NOTICE — DISCLAIMER

- This Bill of Quantities is supplied in good faith based on the BuildEase take-off models for Redcatch Quarter, Knowle, Bristol and the associated Tremco CPG quotation.
- ALL QUANTITIES SHOULD BE INDEPENDENTLY CHECKED AND VERIFIED BY THE PROJECT QS / QUANTITY SURVEYOR before tender submission, ordering or contract award.
- This ICF BOQ does NOT include the external wall finish. The finish is measured, for guidance only, in the finishes / ancillary-trades package of this workbook.
- Section C (Concrete) volumes are geometric voids — allow ~3% web displacement deduction and ~5% wastage on top when ordering ready-mix.
- Section D (Labour) day estimates are scaled proportionately from a reference project; actual gang productivity will vary with site conditions, weather and trade experience.
- BuildEase, Tremco Construction Products Group and Nudura UK accept no liability for tender or contract outcomes arising from the use of these figures. If in doubt — ask.
- Contact: Tom Smith — BuildEase Manager, Nudura UK — for clarification on any quantity or rate basis in this document.

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (top storey) FFL is 5,486 above the GF FFL, ~5.64 m above the adjoining ground (ADB Diagram D6; ground ASSUMED ~150 below GF FFL - each pair of houses is set at the mean existing LiDAR ground + 150, cross-falls regraded by others); ridge ~11.62 m above GF FFL. Top storey BELOW 11 m, so the 11-18 m fire band does not apply; a floor more than 4.5 m above ground needs the ADB Vol 1 protected stairway (or an accepted alternative). 91 terraced dwellings, 3 storeys - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 2A (Approved Document A, houses not exceeding 4 storeys) - engineer to confirm.

NOT FOR CONSTRUCTION. Outline consent only - the house type, levels and openings are BuildEase design assumptions for pricing. The GF slab, strip footings (stepped with the blocks), floors, stairs, roofs, balcony, windows and doors are by others and are NOT in this ICF BOQ (guidance quantities in the finishes / ancillary package). Engineer to design: the strip footings and steps, the UB under the set-back wall, the floor ledgers / hangers on the ICF, the roof trusses and the raked party fins.


CONTENTS

Section	Description	Sheet	Status	
	Cover & Project Information	**Cover**		
	Contents	**Contents**		
	Indicative Programme (Gantt)	**Programme**	*Information*	
	Summary of Tender Pricing	**Summary**		
A	Preliminaries	**A_Preliminaries**	*Contractor priced*	
B	ICF Kit Supply	**B_ICF_Supply**	*Pre-priced*	
C	Concrete Supply, Pump & Placement	**C_Concrete**	*Contractor priced*	
D	Labour — ICF, Floors & Roofs	**D_Labour**	*Contractor priced*	
F	Reference Data (informative only)	**F_Reference**	—	

PROG — INDICATIVE INSTALL PROGRAMME — RESOURCE-LEVELLED, ONE COLUMN PER WORKING DAY

Green = the planner-assembled build sequence, staggered so each block starts when the previous block's first stack is complete. Blue = the same sequence, independently levelled to a realistic crew of 3 erectors and one compressed shutter-moving day. Reassuring until absolutely nothing else is reassuring. Excerpt — continues to 2027. Annotated for clear programmers.

Phase	Plots	Floors	Weeks	Start wk
Block D – 24 houses (D01–D24)	24	5,736	44	1
Block E – 11 houses (E01–E11)	11	1,700	35	6
Block F – 18 houses (F01–F18)	18	2,304	52	10
Block G – 7 houses (G01–G07)	7	1,176	19	65
Block H – 17 houses (H01–H17)	17	2,668	35	54
Block I – 4 houses (I01–I04)	4	796	22	64
Block J – 10 houses (J01–J10)	10	2,208	29	70



LEGEND

	ICF walls — YK and U-Ultz (install helicopter, simulate, study, pivot, curb, strike), ICF going at 3.
	ICF walls + 1st after the 1st floor, 1st joisers, 1st bank wall, gablets, balcony walls, parapet, first [...]
	Concrete pour — plant days from the install estimator, ICF going allready, pump on site
	Curing — pours Wed/Sat Friday where possible, 7 days to strip, 14 days to weatherit, 3 mid-weeks pour cures 2 weeks to strip
	Floors + 1F after 1 C 21 day / yard, 2F + balcony after 1 C 21 days / plots, joinery going off
	Roof and patch — loosest roof after the 12 pour 21 day per yard

RESOURCING

- 2 ICF timber roof 3 manner installers (main crew + 1 four-man-gang-impossible), mess the wall lifts, moving to the next ready block within a floor is flexed, 1 joiners crew of 4 Pro-rumy intermediate floor one roof (joiners going of 3 - 3F floor 1 way per plot, 2F floor + balcony 1.1 days per plot (average) 1 per floor), roof structure 1 day per plot). Programmer to measure levelled day by day (within + block waiting for a crew).
- Team D 1st programmer. 150 working weeks (37 months, floors plot reality. Section 2 Performances are a portfolio against the 150 levels programmer.
- EXTERNAL MASON 1 FINISH IS EXCLUDED hours this BLOC and this programme. Where a render system is later specified, allow a separate workstream — per RIBA guidance, render cannot begin until the concrete core has cured for a minimum of 28 days after the final pour.
- Concrete pump booked on the pour days for each group (see Section F).
- Lead time for Bulldbuse Pre-Cut Service 5–6 weeks from order placement; procurement runs in parallel with mobilisation.
- Programme estimates are provided in good faith and must be verified by the project / site management team.
- PRELUDE: the design must satisfy the Building Regulations 2010 (Approved Documents A–E). · building control by LABC / an approved inspector. Building height: the 2F (top storey) FFL is 5,400 above the GF FFL. · 1 plot at or above the adjoining ground (4200 Dragrave Dr), ground 2010.4693 · 150 below GF FFL · each pair of houses is cut on the mean existing s2100 ground + 150, cross-falls regraded by others); ridge · 12.322 m above GF FFL. Top storey 805.598 12 m, so the 12.150 m first-band does not apply, a floor more than 6.5 m above ground needs the 4200 Set 3 protected stairway (or an accepted alternative). 93 km-band dwellings, 1 storey: · within the LABC Warranty 5-storey limit for 10Y (main-only provider to confirm). Consequence Class 2b (Approved Document A, houses not exceeding 4 storeys) · engineer to confirm.
- Joinery gang of 4. 2F floor 1 day per plot, 2F floor + balcony 1.2 days per plot (the balcony section is time-consuming), roof structure 1 day per plot (pile, net Week 15 21 8 12 7 8 21 7 8 17 14) 23 hours/d). The floors are P333 type metal web joist (22 deck on 333 joists @ 400, parts to pump) top/sway-ey 4F x 225 ridges on the GF main faces, the 2F floor carries a 90 x 140 LVB under the set back wall (engineer). The roof is York trusses @ 600 from the front wall to the set back wall on 2F x 225 plates, natural slate + FS. The GF ground-bearing slab is cast by the groundworker inside the DB qualifications (1 load in the GF/BCE) · coordination quantities in the Bulders_Lines/Secs package).
- Build sequence per block (our client programme issued): FB 2 course on the stepped strip footing by others) · 1 pour · + GF slab (by others) · 1 C 22 F walls (G courses) · 1 pour · + 1F floor · 1 C 2F walls (G courses) · 1 pour · + 2F floor · 1 C 2F walls (G courses) · 1 pour · + 2F floor (+ the GB under the set back wall) · 1 C 2F walls (G courses to the E.250 eaves, set back wall, GT gablets at the block ends, 2 course rear parapet, raised party fire) · 1 pour · + roof. Blocks in the order D, E, F, G, H, I, J (proposal / tube-of-trailer) · to be confirmed with the contractor.
- GT pcs days from the install estimator (wages' gearing, 1 x 7d in retreat rate, new 65 cal per day) work 45% a week 5 days to Friday pours work not the weekend) and stock before the gang moves on.
- PROGRAMME (BCO) Builder sheet "Programme"): ONE GT gang of 4 and ONE joinery gang of 3, blocks in the order D, E, F, G, H, I, J. GT 48 dress are from the BQQ Builder GT install estimator per block and 6B (forms, corners, perimeter, openings), floors, 1 pcs, the one day, pour, cure 3 days, strike 1 day · the going stops with its lift to the circled. The block 7% +1.5 · + 1F floor (1 day per plot) · +1.5 · + 2F floor + balcony (1.2 days per plot) · +1.5 2F walls, gablets, parapet, first) · + roof structure (1 day per plot) a 5% mean starts before the floor below it is complete, and the GT gang moves to the next block while the joiners work behind it. Result: 150 working days + 102 weeks to the last wall, GT gang 201.4 days on the 7%. For block [GT start · last order · roof complete, working days]: D 481 576 -300; E 401 -100 151; F 4111 258 170; G 4151 298 -305; H 4309 415 -515; I 4570 453 615; J 4909 494 510. Concrete in GT pump days. AUXILIARY HIRE + the GT gang's spare run-only, first GT install day (@5) to the last on the [4096] = 102 weeks at the peak 15 colleges @ GBP 90.00 = GBP 135,000.00 (as priced). Programmer estimates are indicative · confirm the sequence and dates with the client / site team.
- Delivery: 60 loads 10 t with 2F 300.0 mi (only 4 180.0 mi+ 302.5(fixed), articulated lorries to Redcatch Road, Knowle, Bristol BS3, block by block in build order, unloading cranes and any transfer to smaller vehicles by the contractor.

SUMMARY OF TENDER PRICING

Section totals are carried forward from each Bill section. Pre-priced columns show values from the associated Tremco CPG quotation; contractor-priced columns populate automatically when rates are entered in the section sheets. This BOQ excludes external render.

Section	Description	Pre-priced (£)	Contractor-priced (£)	Section Total (£)	
A	Preliminaries		£0.00	**£0.00**	
B	ICF Kit Supply	£1,039,141.34		**£1,039,141.34**	
C	Concrete Supply, Pump & Placement		£0.00	**£0.00**	
D	Labour — ICF, Floors & Roofs		£0.00	**£0.00**	
	NET TOTAL (excluding VAT)	**£1,039,141.34**	**£0.00**	**£1,039,141.34**	
	VAT @ 20%			£207,828.27	
	GRAND TOTAL (inclusive of VAT)			**£1,246,969.61**	

SIGNATURES

Priced by					
Tendered by					
Approved by					

A · PRELIMINARIES

Items priced per working week against the site programme total of 102 weeks (see Programme sheet). Quantities are pre-populated; the contractor inserts the weekly rate.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
A.1	Site set-up, fencing, signage, induction & welfare establishment	item	1		£0.00
A.2	Welfare facilities — canteen, drying, toilets (hire)	wk	102		£0.00
A.3	Contract management & site supervision	wk	102		£0.00
A.4	Health & Safety, RAMS, CDM consultancy	wk	102		£0.00
A.5	Public liability and contract works insurance	item	1		£0.00
A.6	Scaffolding — independent access for ICF erection	wk	102		£0.00
A.7	Plant hire — telehandler / forklift for offload & ICF moves	wk	102		£0.00
A.8	Plant hire — small tools, generators, power & lighting	wk	102		£0.00
A.9	Hoarding / site enclosure / security	wk	102		£0.00
A.10	Temporary services — water, power, lighting (hire)	wk	102		£0.00
A.11	Site clean, waste management & skip rotation	wk	102		£0.00
A.12	Setting out and surveying — engineer's level checks	wk	102		£0.00
A.13	Site take-down, hand-over & demobilisation	item	1		£0.00
A.14	Pre-completion sound test (Approved Document E)	test			£0.00
A.15	Air-tightness test (Approved Document L)	test			£0.00
A.16	Day works allowance	sum			£0.00
	A — PRELIMINARIES SUBTOTAL				**£0.00**

B · ICF KIT SUPPLY

ICF material supply values are pre-priced from the associated Tremco CPG quotation. Pre-cut service fees are taken from each BuildEase take-off.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
B.1 — ICF Block, Forms & Accessories					
B.1	ICF Materials — Block D - 24 houses (D01-D24) (24 plot(s), 3,718 forms)	group	1	£216,189.58	£216,189.58
B.1	ICF Materials — Block E - 11 houses (E01-E11) (11 plot(s), 1,759 forms)	group	1	£101,754.70	£101,754.70
B.1	ICF Materials — Block F - 14 houses (F01-F14) (14 plot(s), 2,203 forms)	group	1	£127,703.84	£127,703.84
B.1	ICF Materials — Block G - 7 houses (G01-G07) (7 plot(s), 1,170 forms)	group	1	£67,500.83	£67,500.83
B.1	ICF Materials — Block H - 17 houses (H01-H17) (17 plot(s), 2,648 forms)	group	1	£154,026.44	£154,026.44
B.1	ICF Materials — Block I - 4 houses (I01-I04) (4 plot(s), 706 forms)	group	1	£40,707.89	£40,707.89
B.1	ICF Materials — Block J - 14 houses (J01-J14) (14 plot(s), 2,238 forms)	group	1	£129,569.94	£129,569.94
B.2 — BuildEase Pre-Cut Service Fee					
B.2	Pre-Cut Service — Block D - 24 houses (D01-D24)	group	1	£11,054.06	£11,054.06
B.2	Pre-Cut Service — Block E - 11 houses (E01-E11)	group	1	£5,596.97	£5,596.97
B.2	Pre-Cut Service — Block F - 14 houses (F01-F14)	group	1	£6,829.48	£6,829.48
B.2	Pre-Cut Service — Block G - 7 houses (G01-G07)	group	1	£3,944.12	£3,944.12
B.2	Pre-Cut Service — Block H - 17 houses (H01-H17)	group	1	£8,140.57	£8,140.57
B.2	Pre-Cut Service — Block I - 4 houses (I01-I04)	group	1	£2,680.89	£2,680.89
B.2	Pre-Cut Service — Block J - 14 houses (J01-J14)	group	1	£6,887.33	£6,887.33
B.3 — Haulage					
B.3	Haulage to site — 65 loads: 65 x artic @ 180.0 mi (artic ≤ 180.0 mi = 562.38/load)	item	1	£36,554.70	£36,554.70
B.4 — Alignment System					
B.4	Alignment System Rental — Block D - 24 houses (D01-D24) (294 systems)	group	1	£28,571.42	£28,571.42
B.4	Alignment System Rental — Block E - 11 houses (E01-E11) (152 systems)	group	1	£15,238.10	£15,238.10
B.4	Alignment System Rental — Block F - 14 houses (F01-F14) (191 systems)	group	1	£19,047.62	£19,047.62
B.4	Alignment System Rental — Block G - 7 houses (G01-G07) (101 systems)	group	1	£11,428.57	£11,428.57
B.4	Alignment System Rental — Block H - 17 houses (H01-H17) (212 systems)	group	1	£20,952.38	£20,952.38
B.4	Alignment System Rental — Block I - 4 houses (I01-I04) (63 systems)	group	1	£7,619.05	£7,619.05
B.4	Alignment System Rental — Block J - 14 houses (J01-J14) (164 systems)	group	1	£17,142.86	£17,142.86
	B — ICF KIT SUPPLY SUBTOTAL				**£1,039,141.34**

C · CONCRETE SUPPLY, PUMP & PLACEMENT

Volumes are geometric void calculations (block length × course height × core thickness). Allow ~3% for plastic web displacement and ~5% wastage when ordering. Rates to be inserted by the contractor.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
C.1 — Ready-Mix Concrete Supply (C28/35 typical to BS 8500)					
C.1	Ready-mix concrete — Block D - 24 houses (D01-D24) (24 plot(s), geometric void)	m³	627.79		£0.00
C.1	Ready-mix concrete — Block E - 11 houses (E01-E11) (11 plot(s), geometric void)	m³	294.92		£0.00
C.1	Ready-mix concrete — Block F - 14 houses (F01-F14) (14 plot(s), geometric void)	m³	370.32		£0.00
C.1	Ready-mix concrete — Block G - 7 houses (G01-G07) (7 plot(s), geometric void)	m³	194.65		£0.00
C.1	Ready-mix concrete — Block H - 17 houses (H01-H17) (17 plot(s), geometric void)	m³	445.94		£0.00
C.1	Ready-mix concrete — Block I - 4 houses (I01-I04) (4 plot(s), geometric void)	m³	116.13		£0.00
C.1	Ready-mix concrete — Block J - 14 houses (J01-J14) (14 plot(s), geometric void)	m³	376.21		£0.00
C.2 — Concrete Pump Hire					
C.2	Boom pump hire — Block D - 24 houses (D01-D24)	day	10		£0.00
C.2	Boom pump hire — Block E - 11 houses (E01-E11)	day	7		£0.00
C.2	Boom pump hire — Block F - 14 houses (F01-F14)	day	9		£0.00
C.2	Boom pump hire — Block G - 7 houses (G01-G07)	day	7		£0.00
C.2	Boom pump hire — Block H - 17 houses (H01-H17)	day	10		£0.00
C.2	Boom pump hire — Block I - 4 houses (I01-I04)	day	7		£0.00
C.2	Boom pump hire — Block J - 14 houses (J01-J14)	day	7		£0.00
C.2	Pump mobilisation / demobilisation	item	1		£0.00
C.3 — Concrete Vibration & Placement Plant					
C.3	Internal poker vibrator hire — site duration	wk	102		£0.00
C.3	Concrete banksman / poker operator	day			£0.00
	C — CONCRETE SUBTOTAL				**£0.00**

D · LABOUR — ICF INSTALL, FLOORS & ROOFS

ICF install days scaled proportionately against the Maycroft reference (52.65 forms per gang-day). Rates below are per 4-man gang per day. Floor and roof allowances are taken per group from the project configuration.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
D.1 — ICF Install Gang					
D.1	ICF install — Block D - 24 houses (D01-D24) (3,718 forms ÷ 52.65 forms/day = 70.6 gang-days)	gang-day	70.60		£0.00
D.1	ICF install — Block E - 11 houses (E01-E11) (1,759 forms ÷ 52.65 forms/day = 33.4 gang-days)	gang-day	33.40		£0.00
D.1	ICF install — Block F - 14 houses (F01-F14) (2,203 forms ÷ 52.65 forms/day = 41.8 gang-days)	gang-day	41.80		£0.00
D.1	ICF install — Block G - 7 houses (G01-G07) (1,170 forms ÷ 52.65 forms/day = 22.2 gang-days)	gang-day	22.20		£0.00
D.1	ICF install — Block H - 17 houses (H01-H17) (2,648 forms ÷ 52.65 forms/day = 50.3 gang-days)	gang-day	50.30		£0.00
D.1	ICF install — Block I - 4 houses (I01-I04) (706 forms ÷ 52.65 forms/day = 13.4 gang-days)	gang-day	13.40		£0.00
D.1	ICF install — Block J - 14 houses (J01-J14) (2,238 forms ÷ 52.65 forms/day = 42.5 gang-days)	gang-day	42.50		£0.00
D.1	Snag, pour & cure attendance (30% allowance, project total)	gang-day	82.30		£0.00
D.2 — Floor Structure Labour (1F + 2F metal-web joists top-hung on ICF ledgers; 1F 1 day / plot, 2F + balcony 1.2 days / plot)					
D.2	Floor structure — Block D - 24 houses (D01-D24) (2 floors × 26.4 gang-days)	gang-day	53		£0.00
D.2	Floor structure — Block E - 11 houses (E01-E11) (2 floors × 12.1 gang-days)	gang-day	24		£0.00
D.2	Floor structure — Block F - 14 houses (F01-F14) (2 floors × 15.4 gang-days)	gang-day	31		£0.00
D.2	Floor structure — Block G - 7 houses (G01-G07) (2 floors × 7.7 gang-days)	gang-day	15		£0.00
D.2	Floor structure — Block H - 17 houses (H01-H17) (2 floors × 18.7 gang-days)	gang-day	37		£0.00
D.2	Floor structure — Block I - 4 houses (I01-I04) (2 floors × 4.4 gang-days)	gang-day	9		£0.00
D.2	Floor structure — Block J - 14 houses (J01-J14) (2 floors × 15.4 gang-days)	gang-day	31		£0.00
D.3 — Roof Structure Labour (Fink trusses @ 600 on wall plates, front wall to the set-back wall; 1 day per plot)					
D.3	Roof structure — Block D - 24 houses (D01-D24)	gang-day	24		£0.00
D.3	Roof structure — Block E - 11 houses (E01-E11)	gang-day	11		£0.00
D.3	Roof structure — Block F - 14 houses (F01-F14)	gang-day	14		£0.00
D.3	Roof structure — Block G - 7 houses (G01-G07)	gang-day	7		£0.00
D.3	Roof structure — Block H - 17 houses (H01-H17)	gang-day	17		£0.00
D.3	Roof structure — Block I - 4 houses (I01-I04)	gang-day	4		£0.00
D.3	Roof structure — Block J - 14 houses (J01-J14)	gang-day	14		£0.00
	D — LABOUR SUBTOTAL				**£0.00**

F · REFERENCE DATA (informative only)

Per-group quantities calculated from the BuildEase take-off models. Values feed into Sections C and D. Render is excluded from this BOQ.

Group	Plots	Forms	Concrete (m³)	ICF install days	Floor + Roof days	Pre-cut (£)
Block D - 24 houses (D01-D24)	24	3,718	627.79	70.60	77	£11,054.06
Block E - 11 houses (E01-E11)	11	1,759	294.92	33.40	35	£5,596.97
Block F - 14 houses (F01-F14)	14	2,203	370.32	41.80	45	£6,829.48
Block G - 7 houses (G01-G07)	7	1,170	194.65	22.20	22	£3,944.12
Block H - 17 houses (H01-H17)	17	2,648	445.94	50.30	54	£8,140.57
Block I - 4 houses (I01-I04)	4	706	116.13	13.40	13	£2,680.89
Block J - 14 houses (J01-J14)	14	2,238	376.21	42.50	45	£6,887.33
SITE	**91**	**14,442**	**2,425.95**	**274.30**	**291**	**£45,133.42**

PER-LIFT FORM BREAKDOWN

Group	Lift	4" Std	6" XR35 str	6" XR35 cnr	10" Std	Lift total
Block D - 24 houses (D01-D24)	FB	0	209	4	0	213

Block D - 24 houses (D01-D24)	L1	0	972	24	0	996
Block D - 24 houses (D01-D24)	L2	0	1,023	24	0	1,047
Block D - 24 houses (D01-D24)	L3	0	1,442	20	0	1,462
Block E - 11 houses (E01-E11)	FB	0	91	4	0	95
Block E - 11 houses (E01-E11)	L1	0	450	24	0	474
Block E - 11 houses (E01-E11)	L2	0	469	24	0	493
Block E - 11 houses (E01-E11)	L3	0	678	19	0	697
Block F - 14 houses (F01-F14)	FB	0	113	4	0	117
Block F - 14 houses (F01-F14)	L1	0	567	24	0	591
Block F - 14 houses (F01-F14)	L2	0	596	24	0	620
Block F - 14 houses (F01-F14)	L3	0	855	20	0	875
Block G - 7 houses (G01-G07)	FB	0	60	6	0	66
Block G - 7 houses (G01-G07)	L1	0	291	24	0	315
Block G - 7 houses (G01-G07)	L2	0	305	24	0	329

Block G - 7 houses (G01-G07)	L3	0	440	20	0	460
Block H - 17 houses (H01-H17)	FB	0	142	4	0	146
Block H - 17 houses (H01-H17)	L1	0	686	24	0	710
Block H - 17 houses (H01-H17)	L2	0	724	24	0	748
Block H - 17 houses (H01-H17)	L3	0	1,024	20	0	1,044
Block I - 4 houses (I01-I04)	FB	0	31	4	0	35
Block I - 4 houses (I01-I04)	L1	0	169	24	0	193
Block I - 4 houses (I01-I04)	L2	0	177	24	0	201
Block I - 4 houses (I01-I04)	L3	0	261	16	0	277
Block J - 14 houses (J01-J14)	FB	0	129	4	0	133
Block J - 14 houses (J01-J14)	L1	0	571	24	0	595
Block J - 14 houses (J01-J14)	L2	0	604	24	0	628
Block J - 14 houses (J01-J14)	L3	0	861	21	0	882

GEOMETRIC CONSTANTS & CALCULATION BASIS		
Block length	2.438 m	*96 inches*
Course height	0.4574 m	*18 inches*
4" Std straight volume	0.1133 m³	*Volume = length × course × core*
6" XR35 straight volume	0.1699 m³	*Volume = length × course × core*
10" Std straight volume	0.2832 m³	*Volume = length × course × core*

4" Std corner volume	0.0511 m³	*L-void; long 31.625" / short 15.625"*
6" XR35 corner volume	0.1133 m³	*L-void; long 43" / short 27"*
Maycroft install rate	52.65 forms/day	*Reference: 1053 forms ÷ 20 days*

Bill of Quantities Package - Finishes & Ancillary Trades

ES26-064 | Redcatch Quarter, Knowle, Bristol | Cuckfield Real Estate Ltd

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Project	Redcatch Quarter, Knowle, Bristol
Site	Redcatch Quarter, Redcatch Road, Knowle, Bristol BS4 (91 houses in 7 blocks)
Client	Cuckfield Real Estate Ltd (Ron Persaud)
Drawings	Franklin Ellis 23-0081 outline-consent drawings (block plan 2261 P1, AOD plan 1340 P8, schedule P8, design and access ISO) - house type, levels and openings designed by BuildEase as pricing assumptions
Quotation ref	ES26-064
Document	Bill of Quantities Package - Finishes & Ancillary Trades
Date	10/11/2026
Scope	91 three-storey 3B5P terraced houses in 7 blocks (D 24, E 11, F 14, G 7, H 17, I 4, J 14): 6in XR35 ICF external walls on a 1-course FB on stepped strip footings (by others), 6in Standard party walls, ICF gables at the block ends, rear 2F balcony behind a 1,500 set-back; GF slab, metal-web joist floors, stairs, trussed slate roofs + PV, balcony, windows and doors, linings and fit-out by others
Building height	**ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (top storey) FFL is 5,486 above the GF FFL, ~5.64 m above the adjoining ground (ADB Diagram D6; ground ASSUMED ~150 below GF FFL - each pair of houses is set at the mean existing LiDAR ground + 150, cross-falls regraded by others); ridge ~11.62 m above GF FFL. Top storey BELOW 11 m, so the 11-18 m fire band does not apply; a floor more than 4.5 m above ground needs the ADB Vol 1 protected stairway (or an accepted alternative). 91 terraced dwellings, 3 storeys - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 2A (Approved Document A, houses not exceeding 4 storeys) - engineer to confirm.**
Engineer / specialists	**ENGINEER / SPECIALISTS TO DESIGN: the strip footings and their steps, the floor ledgers / hangers on the ICF, the UB under the 2F set-back wall, the roof trusses, the raked party fins and the balcony build-up; the external finish system and the internal layout are not designed (outline consent). NOT FOR CONSTRUCTION.**
Prepared by	BuildEase (Tremco CPG UK) - BuildEase Design Suite quotation models (one per block)
Status	**FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - rates blank; NOT part of the Nudura ICF price; NOT FOR CONSTRUCTION**

PACKAGE OVERVIEW - pricing by others (all amounts formula-linked to each bill's Package Summary)

Bill	Package	Code / NRM2	Supply £	Install £	Total £
Bill 1	Groundworks & Substructure - Strip Footings, GF Slab, Levels	GRW NRM2 5 / 11 / 34	£0.00	£0.00	£0.00
Bill 2	External Wall Finish to the ICF (system to be confirmed)	EXT NRM2 15 / 21	£0.00	£0.00	£0.00
Bill 3	Opening Schedule - Windows & External Doors (one line per opening type, incl. accessories)	WIN NRM2 25	£0.00	£0.00	£0.00
Bill 4	Floors & Stairs - Metal-Web Joist Floors, Ledgers, Steel, Stairs	FLR / JOI NRM2 16 / 22	£0.00	£0.00	£0.00
Bill 5	Roof Structure - Fink Trusses, Plates, Bracing, Fire-Stopping, Loft Insulation	RFS NRM2 16	£0.00	£0.00	£0.00
Bill 6	Roof Coverings & Rainwater - Natural Slate, Eaves, Verges, Step Abutments, Gutters, PV	RFC NRM2 18 / 33	£0.00	£0.00	£0.00
Bill 7	Balcony - Warm Deck, Waterproofing, Paving, Copings, Balustrade	BAL NRM2 18 / 22	£0.00	£0.00	£0.00
Bill 8	Internal Linings - ICF and Party Wall Faces, Ceilings, Reveals	DRY NRM2 28	£0.00	£0.00	£0.00
Bill 9	Internal Fit-Out - Partitions, Doors, Joinery, Kitchens, Sanitaryware (PROVISIONAL per dwelling)	JOI NRM2 16 / 22 / 24	£0.00	£0.00	£0.00
Bill 10	Services - Electrical & Mechanical (PROVISIONAL per dwelling)	M&E NRM2 38-40	£0.00	£0.00	£0.00
Bill 11	Design, Approvals, Surveys & Certification	DES -	£0.00	£0.00	£0.00
	GRAND TOTAL - finishes / ancillary trades, net (excl. VAT)		**£0.00**	**£0.00**	**£0.00**

Optional additions (enter %; blank = 0)		**%**		**Amount £**
Preliminaries	on the finishes net grand total			£0.00
Overheads & profit	on net total + preliminaries			£0.00
Contingency	on net total + preliminaries + OH&P			£0.00
	GRAND TOTAL finishes incl. preliminaries, OH&P and contingency (excl. VAT)			**£0.00**

ICF PACKAGE HOOK - BuildEase BOQ Builder (ICF kit, concrete, labour, preliminaries, programme)	
Nudura ICF package (BuildEase BOQ Builder sheets of this workbook: Summary NET TOTAL)	£1,039,141.34
COMBINED TOTAL - finishes package (incl. additions) + ICF package, excl. VAT	**£1,039,141.34**

Pale-yellow cells are the only inputs (rates on each bill sheet, percentages and the ICF hook here). Everything else is a locked formula (protection has no password). Schedules A to D are reference only and are not priced. Named cells: FINISHES_NET_TOTAL, FINISHES_GRAND_TOTAL, ICF_PACKAGE_TOTAL, COMBINED_TOTAL.

IMPORTANT - This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

KEY QUANTITIES (site totals: 7 blocks / 91 houses, net; linked to the bills)		
External finish on the ICF outer face (net, excl. reveals)	6,801.24	m2
Strip footings under the ICF (external + party)	1,683.48	m
GF ground-bearing slab	3,286.48	m2
Windows	728.00	nr
External doorsets	273.00	nr
1F + 2F floor decks (net)	5,728.05	m2
Metal-web joists	2,912.00	nr
Staircase flights	182.00	nr
Fink trusses	637.00	nr
Natural slate on the slope	4,393.85	m2
Balcony decks	391.73	m2
Wall linings (ICF + party faces, reveals)	17,154.98	m2
Ceilings and stair soffits	9,536.20	m2
Dwellings	91.00	nr

Document control

Document	Description	Date	By / Status
Quotation	Finishes / ancillary-trades BOQ package for the Nudura ICF quotation (one column per block D to J, 91 houses), merged with the BuildEase BOQ Builder ICF bill + programme. Live pricing workbook: rates blank for pricing by others; ICF_PACKAGE_TOTAL linked to the BOQ Builder NET TOTAL	10/11/2026	BuildEase - T. Smith / For information / pricing by others - NOT FOR CONSTRUCTION

Contents

Finishes Cover (this sheet) - overview
General Notes
Summary of Bills (section breakdown)
Bill 1 Groundworks
Bill 2 External Finish
Bill 3 Opening Schedule
Bill 4 Floors & Stairs
Bill 5 Roof Structure
Bill 6 Roof Coverings
Bill 7 Balcony
Bill 8 Internal Linings
Bill 9 Fit-Out
Bill 10 Services
Bill 11 Design & Approvals
Schedule A Areas (not priced)
Schedule B Openings (not priced)
Schedule C Per Block (not priced)
Schedule D Levels (not priced)

General Notes, Measurement Basis, Assumptions & Exclusions

ES26-064 | Redcatch Quarter, Knowle, Bristol | Cuckfield Real Estate Ltd

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

1 Purpose and status

This package presents the finishes and ancillary-trade quantities measured by BuildEase alongside the Nudura ICF quotation for Redcatch Quarter, Knowle, Bristol (ref ES26-064). It is set out as a Bill of Quantities split by PACKAGE (one bill per trade) so that the client, their quantity surveyor and trade contractors can price and coordinate the works: each line has a quantity per block, a Site total, a SUPPLY rate and an INSTALL rate.

1.1

Status: FOR INFORMATION, COORDINATION AND PRICING BY OTHERS. Supply and install rates are left blank deliberately - BuildEase / Tremco CPG are not pricing these trades. The Excel workbook is a live pricing document: enter rates and every amount, section subtotal, package total and the cover overview update by formula.

1.2

The ICF kit, concrete core, pumping, ICF / floor / roof labour, ICF preliminaries and the build programme are in the BuildEase BOQ Builder sheets of the merged workbook (Cover, Contents, Programme, Summary, A-D, F). The finishes cover carries a named hook (ICF_PACKAGE_TOTAL) linked to the BOQ Builder NET TOTAL.

1.3

This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price.

1.4

Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

1.5

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (top storey) FFL is 5,486 above the GF FFL, ~5.64 m above the adjoining ground (ADB Diagram D6; ground ASSUMED ~150 below GF FFL - each pair of houses is set at the mean existing LiDAR ground + 150, cross-falls regraded by others); ridge ~11.62 m above GF FFL. Top storey BELOW 11 m, so the 11-18 m fire band does not apply; a floor more than 4.5 m above ground needs the ADB Vol 1 protected stairway (or an accepted alternative). 91 terraced dwellings, 3 storeys - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 2A (Approved Document A, houses not exceeding 4 storeys) - engineer to confirm.

1.6

2 Basis of measurement

Measured generally in accordance with the principles of NRM2 (RICS New Rules of Measurement, Detailed measurement for building works): work measured net as fixed in position, items grouped by work section, units m / m2 / nr / item. NRM2 is referenced for structure only; descriptions are BuildEase's own.

2.1

Quantities are NET. No allowance for waste, laps, cutting or breakage is included unless stated. Where useful an "Order guide" with a stated waste % is given in the Notes column; it is guidance only. Lines marked "guide" or "not priced" are ordering guides and must not be priced.

2.2

Quantity columns: one column PER BLOCK - D (24 houses, D01-D24), E (11), F (14), G (7), H (17), I (4), J (14) = 91 houses; plots numbered from the low end of each block. The Site total = SUMPRODUCT(block multipliers, block quantities) - a live formula (multipliers 1). End houses (gables) differ from mid-terrace houses; Schedule A gives both, Schedule C the key quantities per block.

2.3

Sources: the outline-consent drawings (Franklin Ellis 23-0081 outline-consent drawings (block plan 2261 P1, AOD plan 1340 P8, schedule P8, design and access ISO) - house type, levels and openings designed by BuildEase as pricing assumptions); the BuildEase quotation models, one per block (03_Models RC_B<k>), through their specs (04_Logs/specs RC_spec_B<k>.json - levels, openings, steps), the site placing (04_Logs/site/site_place.json), the LiDAR levels (RC_levels.json) and the house dressing (05_Scripts/rc_dress.rb: floors, stairs, trusses, slate, balcony, windows). Measured offline by 05_Scripts/rc_xi_takeoff.py; presented by rc_boq.py.

2.4

3 Assumptions (house type designed by BuildEase on an outline consent)

House: 3B5P three-storey terraced house, 4,080 wide (plot centres) x 10,312.4 deep, floor-to-floor 2,743.2 (6 courses), eaves 8,229.6, 35 deg duo-pitch slate roof per party bay, ridge ~11,618. Rear 2F balcony: the top-floor rear wall SET BACK 1,500 (outer face y 8,812.4), the party walls run on as raked 6in Standard fins, a 2-course (914) 6in XR35 parapet on the rear face. ICF gables at the block ends. Rear single-storey outriggers and front porches are NOT included (by others).

3.1

Walls: external 6in XR35 (355.6, 4in EPS both faces) on every level incl. the FB course; party walls 6in Standard. Window / door frames tight behind the outer EPS (102 external reveal); internal reveal 211.5 (ICF less outer EPS less a 70 frame plus a 27.5 lining).

3.2

Levels: FFL per pair of houses = mean existing ground (EA LiDAR) + 150, stepping a whole course (457.2) at the party walls: 12 step lines (D 4, E 1, F 1, G 1, H 2, I 0, J 3); front-to-rear cross-falls regraded by others. DPC taken at FFL - 150.

3.3

Openings (11 per house, design assumptions): front door 1,010, GF window 1,200, two 1F and two 2F front windows 1,050, rear patio doors 1,800, two 1F rear windows 1,050, a 2F set-back window 1,050 and a 900 balcony door. Sizes, sills and heads to be confirmed from a window schedule.

3.4

Floors (1F, 2F): metal-web joists top-hung on ledgers on the ICF; roof: Fink trusses @ 600 front wall to set-back wall; stairs: two straight flights per house. These are BuildEase's indicative designs in the 3D model - the floor / truss / stair designers and the engineer confirm.

3.5

External finish system not chosen (no elevations): measured once on the ICF outer face and priced for whichever system is selected (Bill 2).

3.6

4 Exclusions (not measured in this package)

Nudura ICF formwork and accessories (in the Nudura price - see section 6). Concrete core, pumping, ICF / floor / roof labour and ICF preliminaries are in the BuildEase BOQ Builder sheets of this workbook.

4.1

Apartments, commercial units, rear outriggers, front porches / pergolas, garages, external works other than as Bill 1C, landscaping, roads and sewers, statutory undertakers' connections and off-site works.

4.2

Items in Bills 9 and 10 are PROVISIONAL per-dwelling allowances (no internal layout or services design exists) - they are not measured quantities.

4.3

Scaffolding for the finishing trades after the ICF (the ICF BOQ Builder preliminaries carry ICF access only), VAT, fees except as Bill 11.

4.4

5 Items to be confirmed

The whole house type (plans, elevations, openings, levels) is a BuildEase pricing assumption on an outline consent - re-measure on the detailed design.

5.1

External finish system (Bill 2) and, if a brick outer leaf is chosen, its support on the strip footing and the wall ties into the ICF (changes the set-out).

5.2

Proposed levels: the stepped FFLs and the cross-fall regrade (1C) come from LiDAR existing ground - re-measure on the designed levels.

5.3

Site closers / voids at detailed design (ICF package): the step apex on the stepped party walls (2F) and a 48 mm closer at one block D step.

5.4

Rainwater: the rear downpipe of each house passes the balcony (outlet + downpipe route to be designed); PV extent per SAP.

5.5

Protected stairway / fire strategy for the 3-storey houses; Consequence Class and the UB under the set-back wall (engineer).

5.6

6 What IS in the Nudura price (Quotation ES26-064)

Nudura pre-cut ICF kit for the 7 blocks / 91 houses as modelled in the BuildEase Design Suite (one model and take-off per block, stepped FB): NET GBP 1,039,141.34 = materials 837,453.22 + BuildEase Pre-Cut Service 45,133.42 + alignment system hire 120,000.00 + haulage 36,554.70 (excl. VAT).

6.1

6.2 Accessories: VJC clips, spray foam, Form-Lock and T-form support straps, end caps and lintel closures.

BuildEase Pre-Cut Service: design, coordination, installation drawings, pre-cutting and packaging of forms, field services support.

6.3

6.4 Nothing in Bills 1 to 11 of this package is included in the Nudura price.

7 Programme and alignment (summary of the BOQ Builder Programme sheet)

PROGRAMME (BOQ Builder sheet 'Programme'): ONE ICF gang of 4 and ONE joinery gang of 4, blocks in the order D, E, F, G, H, I, J. ICF lift times are from the BOQ Builder ICF install estimator per block and lift (forms, corners, perimeter, openings / lintels / props, the snag day, pour, cure 2 days, strike 1 day - the gang stays with its lift to the strike). Per block: FB -> L1 -> 1F floor (1 day per plot) -> L2 -> 2F floor + balcony (1.2 days per plot) -> L3 (2F walls, gables, parapet, fins) -> roof structure (1 day per plot); a lift never starts before the floor below it is complete, and the ICF gang moves to the next block while the joiners work behind it. Result: 510 working days = 102 weeks to the last roof; ICF gang 451.6 days on the lifts. Per block (ICF start - last strike - roof complete, working days): D d0-176-200; E d41-191-211; F d111-256-270; G d211-296-303; H d269-401-418; I d319-411-422; J d369-496-510. Concrete in 57 pump days. ALIGNMENT HIRE = the ICF gang's span on site, first ICF install day (d0) to the last strike (d496) = 100 weeks at the peak 15 stillages @ GBP 80.00 = GBP 120,000.00 (as priced). Programme estimates are indicative - confirm the sequence and dates with the client / site team.

7.1

8 Pricing instructions to tenderers

Each bill item has a SUPPLY rate and an INSTALL rate. Insert rates only in the pale-yellow cells of the Excel workbook: Supply = Site total qty x Supply rate; Install = Site total qty x Install rate; Line total = Supply + Install. Items measured as "item" without a quantity are lump sums: the rate entered is the amount.

8.1

Each bill ends with a Package Summary (section subtotals for Supply / Install / Total and the package total). The finishes Cover carries the full overview: one row per bill, grand totals, optional Preliminaries, Overheads & profit and Contingency percentages (pale-yellow cells; blank = 0) and the ICF package hook.

8.2

All other cells are locked by sheet protection (no password - Review > Unprotect Sheet if a change is genuinely needed) so formulas cannot be overwritten by accident.

8.3

Re-measure and verify all quantities before pricing or ordering. State any qualification against the item in the Notes column.

8.4

The Order guide figures, guide lines and Schedules A to D are not measured bill items and must not be priced as such. All amounts exclude VAT.

8.5

Summary of Bills - section breakdown

ES26-064 | Redcatch Quarter, Knowle, Bristol | Cuckfield Real Estate Ltd - amounts by others, excl. VAT

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Bill	Section	Description	Supply £	Install £	Total £
1	1A	Substructure - strip footings under the ICF (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	£0.00
1	1B	GF ground-bearing slab inside the FB walls (NRM2 11 - package GRW; engineer)	£0.00	£0.00	£0.00
1	1C	Levels, drainage and sloping plots (NRM2 34 / 37 - package EXT; PROVISIONAL)	£0.00	£0.00	£0.00
Bill 1 - Groundworks & Substructure - Strip Footings, GF Slab, Levels (package GRW)			**£0.00**	**£0.00**	**£0.00**
2	2A	External wall finish to the ICF outer face (NRM2 15 / 21 - package EXT; system TO BE CONFIRMED by the architect)	£0.00	£0.00	£0.00
2	2B	Trims, beads and joints (NRM2 21 - package EXT)	£0.00	£0.00	£0.00
Bill 2 - External Wall Finish to the ICF (system to be confirmed) (package EXT)			**£0.00**	**£0.00**	**£0.00**
3	3A	Opening schedule - windows and external doors, one line per opening type incl. accessories (NRM2 25 - package WIN; supplier)	£0.00	£0.00	£0.00
Bill 3 - Opening Schedule - Windows & External Doors (one line per opening type, incl			**£0.00**	**£0.00**	**£0.00**
4	4A	1F and 2F floors - metal-web joists top-hung on the ICF (NRM2 16 - package FLR; floor designer / engineer)	£0.00	£0.00	£0.00
4	4B	Stairs (NRM2 22 - package JOI; stair manufacturer)	£0.00	£0.00	£0.00
Bill 4 - Floors & Stairs - Metal-Web Joist Floors, Ledgers, Steel, Stairs (package FLR / JO			**£0.00**	**£0.00**	**£0.00**
5	5A	Roof structure - trussed roof (NRM2 16 - package RFS; truss designer / engineer)	£0.00	£0.00	£0.00
Bill 5 - Roof Structure - Fink Trusses, Plates, Bracing, Fire-Stopping, Loft Insulation (			**£0.00**	**£0.00**	**£0.00**
6	6A	Roof coverings, eaves, verges and abutments (NRM2 18 - package RFC)	£0.00	£0.00	£0.00
6	6B	Rainwater goods (NRM2 33 - package RFC)	£0.00	£0.00	£0.00
6	6C	Solar PV (NRM2 - package M&E; PROVISIONAL)	£0.00	£0.00	£0.00
Bill 6 - Roof Coverings & Rainwater - Natural Slate, Eaves, Verges, Step Abutments, Gu			**£0.00**	**£0.00**	**£0.00**
7	7A	Rear 2F balcony behind the 1,500 set-back (NRM2 18 / 22 - package BAL; designer)	£0.00	£0.00	£0.00
Bill 7 - Balcony - Warm Deck, Waterproofing, Paving, Copings, Balustrade (package BA			**£0.00**	**£0.00**	**£0.00**
8	8A	Wall linings (NRM2 28 - package DRY)	£0.00	£0.00	£0.00
8	8B	Ceilings (NRM2 28 - package DRY)	£0.00	£0.00	£0.00
8	8C	Jointing, beads and skim (NRM2 28 - package DRY)	£0.00	£0.00	£0.00
Bill 8 - Internal Linings - ICF and Party Wall Faces, Ceilings, Reveals (package DRY)			**£0.00**	**£0.00**	**£0.00**
9	9A	Internal layout - PROVISIONAL per dwelling (NRM2 16 / 24 / 22 - package JOI; layout NOT designed)	£0.00	£0.00	£0.00
9	9B	Second-fix joinery measured from the model (NRM2 22 - package JOI)	£0.00	£0.00	£0.00
Bill 9 - Internal Fit-Out - Partitions, Doors, Joinery, Kitchens, Sanitaryware (PROVISI			**£0.00**	**£0.00**	**£0.00**
10	10A	Mechanical and electrical services - PROVISIONAL per dwelling (NRM2 38 / 39 / 40 - package M&E; M&E designer)	£0.00	£0.00	£0.00
Bill 10 - Services - Electrical & Mechanical (PROVISIONAL per dwelling) (package M&E			**£0.00**	**£0.00**	**£0.00**
11	11A	Design, approvals, surveys and certification (package DES; by the client / their consultants)	£0.00	£0.00	£0.00
Bill 11 - Design, Approvals, Surveys & Certification (package DES)			**£0.00**	**£0.00**	**£0.00**
TOTAL - finishes / ancillary trades, net (agrees with the Cover overview)			**£0.00**	**£0.00**	**£0.00**

Schedules A to D are reference schedules and are not priced. Preliminaries, overheads & profit, contingency and the ICF package (BuildEase BOQ Builder) are applied on the Cover.

Bill 1 - Groundworks & Substructure - Strip Footings, GF Slab, Levels

Strip footings under the ICF (stepped), the GF ground-bearing slab and the levels / drainage interfaces - all by others; coordination quantities. [NRM2 5 / 11 / 34 / package GRW]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and t		1	1	1	1	1	1	1	7						
1A	**Substructure - strip footings under the ICF (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)**															
	The ICF FB course (1 course 6in XR35, 457.2 high, -457.2 to GF FFL) stands on a concrete strip footing BY OTHERS (size / reinforcement by the engineer - not modelled) under the external walls and the 6in Standard party walls. The blocks STEP a whole course (457.2) at 12 party lines (D 4, E 1, F 1, G 1, H 2, I 0, J 3); the house on the high side of each step carries a second FB course on its front / rear walls, so the footing steps at the far party line. A brick outer leaf, if chosen (Bill 2), is also carried by the strip footing.															
1A.1	Concrete strip footing under the external ICF walls (front, rear, gable ends) - ICF centre-line length; width, depth and reinforcement by the engineer	m	215.04	108.96	133.44	76.32	157.92	51.84	133.44	**876.97**			£0.00	£0.00	**£0.00**	Stepped with the blocks
1A.2	Concrete strip footing under the 6in Standard ICF party walls (between the external wall footings)	m	220.83	96.01	124.82	57.61	153.62	28.80	124.82	**806.50**			£0.00	£0.00	**£0.00**	9.60 m per party wall
1A.3	Step in the strip footing, 457 rise, at a step party line (front and rear external walls)	nr	8.00	2.00	2.00	2.00	4.00		6.00	**24.00**			£0.00	£0.00	**£0.00**	2 per step line; the party wall footing on a step line is level at the lower house
1A.4	Protection board / DPM to the FB outer EPS face below ground (approx. 300 below DPC) and backfill against the FB walls	m	216.47	110.39	134.87	77.75	159.35	53.27	134.87	**886.94**			£0.00	£0.00	**£0.00**	Building outline at the ICF outer faces
1A.5	Excavation, disposal, earthwork support and dewatering for the footings - per block (engineer / SI)	item	1.00	1.00	1.00	1.00	1.00	1.00	1.00	**7.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - no site investigation issued
1A.6	Radon / ground-gas protection (membrane + sealed service entries) IF the site investigation requires - per block	item	1.00	1.00	1.00	1.00	1.00	1.00	1.00	**7.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - Knowle, Bristol: check the radon map / SI
1B	**GF ground-bearing slab inside the FB walls (NRM2 11 - package GRW; engineer)**															
	Per house inside the ICF inner faces (party to party / gable, front to rear): 36.43 m2 mid-terrace, 34.39 m2 end house. Modelled (rc_dress) as an indicative 85 slab + 65 screed at -150 to 0; build-up, insulation and DPM / radon barrier lapped to the ICF by the engineer / designer (Part C / L).															
1B.1	150 compacted hardcore sub-base, blinded	m2	870.22	396.64	505.93	250.92	615.21	141.63	505.93	**3,286.48**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,615.1
1B.2	DPM / radon barrier, lapped and sealed to the ICF (dressed up the inner EPS face to DPC)	m2	870.22	396.64	505.93	250.92	615.21	141.63	505.93	**3,286.48**			£0.00	£0.00	**£0.00**	Order guide +15% = 3,779.4
1B.3	Floor insulation (PIR, thickness to Part L / SAP) under the slab or screed	m2	870.22	396.64	505.93	250.92	615.21	141.63	505.93	**3,286.48**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,615.1
1B.4	Ground-bearing concrete slab (thickness / mesh by the engineer)	m2	870.22	396.64	505.93	250.92	615.21	141.63	505.93	**3,286.48**			£0.00	£0.00	**£0.00**	At 150 thick = 493.0 m3 (guide)
1B.5	Sand-cement or flowing screed 65 to the GF	m2	870.22	396.64	505.93	250.92	615.21	141.63	505.93	**3,286.48**			£0.00	£0.00	**£0.00**	
1B.6	Perimeter edge insulation upstand at the slab / screed edge against the ICF	m	642.13	293.85	374.22	186.69	454.59	106.31	374.22	**2,432.02**			£0.00	£0.00	**£0.00**	Order guide +10% = 2,675.2
1C	**Levels, drainage and sloping plots (NRM2 34 / 37 - package EXT; PROVISIONAL)**															
	No proposed levels exist. Each pair of houses is set at the mean existing ground (EA LiDAR 1 m DTM) + 150, stepping a whole course at the party walls; the front-to-rear cross-fall (0.2 - 0.7 m) is REGRADED BY OTHERS. 1C.1 / 1C.2 are measured on the existing ground along both long faces of every plot (Schedule D) - re-measure on the designed external levels.															
1C.1	Exposed ICF face between DPC (FFL-150) and existing ground on the low side: continue the external finish / plinth protection down to finished ground - or make up the ground	m2	14.63	24.20	28.53	4.97	5.31	0.94	24.08	**102.66**			£0.00	£0.00	**£0.00**	Existing ground, front + rear faces
1C.2	Existing ground above DPC against the ICF on the high side: regrade to 150 below DPC (or tank / protect the ICF face and add perimeter drainage)	m2	24.79	6.26	10.41	5.85	13.43	4.00	17.05	**81.79**			£0.00	£0.00	**£0.00**	Existing ground, front + rear faces
1C.3	Regrade the front-to-rear cross-fall to the stepped FFLs (cut / fill, retaining edges where needed) - per block	item	1.00	1.00	1.00	1.00	1.00	1.00	1.00	**7.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - external works design by others
1C.4	Rainwater drainage connections at the downpipe shoes (gullies / rest bends to the surface water system)	nr	48.00	22.00	28.00	14.00	34.00	8.00	28.00	**182.00**			£0.00	£0.00	**£0.00**	1 front + 1 rear per house
1C.5	Foul drainage connection per dwelling (soil stack to the below-ground drainage, inspection chamber)	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL

PACKAGE SUMMARY - Bill 1 Groundworks & Substructure - Strip Footings, GF Slab, Levels (package GRW; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
1A	Substructure - strip footings under the ICF (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	**£0.00**
1B	GF ground-bearing slab inside the FB walls (NRM2 11 - package GRW; engineer)	£0.00	£0.00	**£0.00**
1C	Levels, drainage and sloping plots (NRM2 34 / 37 - package EXT; PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 1, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 2 - External Wall Finish to the ICF (system to be confirmed)

Finish to the outer EPS face of the 6in XR35 ICF walls, net of openings, with reveals, beads and joints. System by the architect. [NRM2 15 / 21 / package EXT]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		1	1	1	1	1	1	1	7						
2A	**External wall finish to the ICF outer face (NRM2 15 / 21 - package EXT; system TO BE CONFIRMED by the architect)**															
	No elevations exist (outline consent). The finish is measured on the outer EPS face of the 6in XR35 ICF, net of the structural openings, from DPC (FFL - 150) - system to be chosen at detailed design: e.g. a through-coloured / silicone render on the XR35 EPS (BBA, mesh + base coat), a brick-slip system on the EPS, or a facing-brick outer leaf on the strip footing tied to the ICF (that changes the set-out). The rates entered should be for the chosen system.															
2A.1	External finish to walls - Front elevation, DPC to the eaves (8,230), net of openings	m2	591.05	270.90	344.78	172.39	418.66	98.51	344.78	**2,241.08**			£0.00	£0.00	**£0.00**	Order guide +10% = 2,465.2
2A.2	External finish to walls - Rear elevation, DPC to the top of the 2-course balcony parapet (6,401), net of openings	m2	480.15	220.07	280.09	140.05	340.11	80.03	280.09	**1,820.59**			£0.00	£0.00	**£0.00**	Order guide +10% = 2,002.6
2A.3	External finish to walls - 2F set-back wall onto the balcony (5,486 to 8,230), net of openings	m2	171.83	78.12	99.75	49.29	121.37	27.67	99.75	**647.76**			£0.00	£0.00	**£0.00**	Order guide +10% = 712.5
2A.4	External finish to walls - Gable ends at the block ends, DPC to the raked verge / apex trim (10,973) incl. the raked balcony fin, net of openings	m2	198.08	198.08	198.08	198.08	198.08	198.08	198.08	**1,386.59**			£0.00	£0.00	**£0.00**	Order guide +10% = 1,525.2
2A.5	External finish to walls - Balcony: inner faces of the parapet and the raked party / gable fins above the deck, net of openings	m2	186.32	85.19	108.53	54.07	131.87	30.73	108.53	**705.23**			£0.00	£0.00	**£0.00**	Order guide +10% = 775.8
2A.6	Finish to the external reveals (jambs, heads; window frames tight behind the 102 outer EPS)	m2	113.88	52.20	66.43	33.22	80.66	18.98	66.43	**431.79**			£0.00	£0.00	**£0.00**	Order guide +10% = 475.0
2A.7	Finish to the party-wall upstand faces exposed above the lower roof at the roof steps	m2	19.67	4.92	4.92	4.92	9.84		14.76	**59.02**			£0.00	£0.00	**£0.00**	One course high along the roof line at each step line
2B	**Trims, beads and joints (NRM2 21 - package EXT)**															
2B.1	Corner beads / returns at the building external corners (gable ends, full height)	m	29.86	29.86	29.86	29.86	29.86	29.86	29.86	**209.03**			£0.00	£0.00	**£0.00**	Order guide +10% = 229.9
2B.2	Reveal beads / stop beads round the window and door openings (jambs and heads)	m	1,120.86	513.73	653.83	326.92	793.94	186.81	653.83	**4,249.92**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,674.9
2B.3	Base / starter track at DPC with drip (render) or base support (slips) on the outer faces	m	216.47	110.39	134.87	77.75	159.35	53.27	134.87	**886.94**			£0.00	£0.00	**£0.00**	Order guide +10% = 975.6
2B.4	Head stop at the eaves soffits (front eaves, set-back eaves over the balcony)	m	188.56	86.19	109.81	54.69	133.44	31.07	109.81	**713.58**			£0.00	£0.00	**£0.00**	Order guide +10% = 784.9
2B.5	Head stop / closer under the verge and along the raked balcony fin at the gable ends	m	20.95	20.95	20.95	20.95	20.95	20.95	20.95	**146.63**			£0.00	£0.00	**£0.00**	Order guide +10% = 161.3
2B.6	Vertical movement joint at each party-wall line on the front and rear faces, full height (backer rod + sealant)	m	343.40	149.30	194.10	89.58	238.89	44.79	194.10	**1,254.15**			£0.00	£0.00	**£0.00**	Positions / spacing to the finish-system supplier

PACKAGE SUMMARY - Bill 2 External Wall Finish to the ICF (system to be confirmed) (package EXT; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
2A	External wall finish to the ICF outer face (NRM2 15 / 21 - package EXT; system TO BE CONFIRMED by the architect)	£0.00	£0.00	**£0.00**
2B	Trims, beads and joints (NRM2 21 - package EXT)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 2, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

BuildEase

Bill 3 - Opening Schedule - Windows & External Doors (one line per opening type, incl. accessories)

Windows and external doorsets as a QS schedule: one line per opening type with its accessories, quantity per block. Supply + install by others. [NRM2 25 / package WIN]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		1	1	1	1	1	1	1	7						
3A	**Opening schedule - windows and external doors, one line per opening type incl. accessories (NRM2 25 - package WIN; supplier)**															
	Every house has the same 11 openings (spec openings, mirrored per handing): structural opening (SO) per line, quantity = houses per block. Each line includes the frame, double / triple glazing to Part L, fixing straps into the ICF webs, INTERNAL airtightness tape and EXTERNAL weather membrane / sealant round the frame (perimeter in the Notes), the external cill (windows: uPVC / aluminium, 40 projection), trickle vents to Part F (windows) and safety glazing where required. Frames tight behind the 4in outer EPS (overfly 25 on the head + jambs). Windows in a 1F room with a sill below 800 above FFL need guarding (Part K): toughened / laminated lower pane or a fixed guard + restrictor.															
3A.1	D1 GF front - front door 1,010 SO (composite, level threshold): Front entrance doorset, composite, level threshold (Part M), multi-point lock, PAS 24 / Secured by Design, letter plate, viewer; SO 1,010 x 2,134	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 0 / head 2,134 above FFL; tapes 6.29 m per opening
3A.2	W1 GF front - GF front window (kitchen): Window, uPVC / alu-clad casement, 2 lights, trickle vents; SO 1,200 x 1,372	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 762 / head 2,134 above FFL; tapes 5.14 m per opening; cill 1.24 m
3A.3	D2 GF rear - GF rear patio doors 1,800 SO: Rear patio doorset, 2-leaf (French or sliding), uPVC / alu-clad, low threshold, PAS 24, toughened safety glass; SO 1,800 x 2,134	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 0 / head 2,134 above FFL; tapes 7.87 m per opening
3A.4	W2 1F front - 1F front (living): Window, uPVC / alu-clad casement, 1 light, trickle vents, sill 762 above FFL - Part K guarding / restrictor; SO 1,050 x 1,524	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 762 / head 2,286 above FFL; tapes 5.15 m per opening; cill 1.09 m
3A.5	W3 1F front - 1F front (living): Window, uPVC / alu-clad casement, 1 light, trickle vents, sill 762 above FFL - Part K guarding / restrictor; SO 1,050 x 1,524	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 762 / head 2,286 above FFL; tapes 5.15 m per opening; cill 1.09 m
3A.6	W6 1F rear - 1F rear (bed 1): Window, uPVC / alu-clad casement, 1 light, trickle vents, sill 762 above FFL - Part K guarding / restrictor; SO 1,050 x 1,372	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 762 / head 2,134 above FFL; tapes 4.84 m per opening; cill 1.09 m
3A.7	W7 1F rear - 1F rear (bath): Window, uPVC / alu-clad casement, 1 light, trickle vents, OBSCURE glass, sill 762 above FFL - Part K guarding / restrictor; SO 1,050 x 1,372	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 762 / head 2,134 above FFL; tapes 4.84 m per opening; cill 1.09 m
3A.8	W4 2F front - 2F front (bed 2): Window, uPVC / alu-clad casement, 1 light, trickle vents; SO 1,050 x 1,219	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 914 / head 2,134 above FFL; tapes 4.54 m per opening; cill 1.09 m
3A.9	W5 2F front - 2F front (bed 3): Window, uPVC / alu-clad casement, 1 light, trickle vents; SO 1,050 x 1,219	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 914 / head 2,134 above FFL; tapes 4.54 m per opening; cill 1.09 m
3A.10	D3 2F set-back (balcony) - 2F balcony door 900 SO (level threshold onto the balcony deck): Balcony doorset, single leaf, uPVC / alu-clad, level threshold with an upstand / drainage channel onto the balcony deck, PAS 24, toughened glass; SO 900 x 2,134	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 0 / head 2,134 above FFL; tapes 6.07 m per opening
3A.11	W8 2F set-back (balcony) - 2F rear (bed 2/3): Window, uPVC / alu-clad casement, 1 light, trickle vents; SO 1,050 x 1,219	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	Sill 914 / head 2,134 above FFL; tapes 4.54 m per opening; cill 1.09 m
3B	**Accessory totals (ordering guide - included in the 3A lines, not priced again)**															
3B.1	*Airtightness tape (internal) and weather membrane / sealant (external) round the frames - each*	*m*	*1,415.10*	*648.59*	*825.47*	*412.74*	*1,002.36*	*235.85*	*825.47*	*5,365.58*					*not priced*	*Order guide +10% = 5,902.1 (guide only)*
3B.2	*External window cills (SO width + 40)*	*m*	*212.88*	*97.57*	*124.18*	*62.09*	*150.79*	*35.48*	*124.18*	*807.17*					*not priced*	*Guide only*
3B.3	*Windows - total*	*nr*	*192.00*	*88.00*	*112.00*	*56.00*	*136.00*	*32.00*	*112.00*	*728.00*					*not priced*	*Guide only*
3B.4	*External doorsets - total (front, patio, balcony)*	*nr*	*72.00*	*33.00*	*42.00*	*21.00*	*51.00*	*12.00*	*42.00*	*273.00*					*not priced*	*Guide only*

PACKAGE SUMMARY - Bill 3 Opening Schedule - Windows & External Doors (one line per opening type, incl. accessories) (package WIN; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
3A	Opening schedule - windows and external doors, one line per opening type incl. accessories (NRM2 25 - package WIN; supplier)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 3, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 4 - Floors & Stairs - Metal-Web Joist Floors, Ledgers, Steel, Stairs

1F and 2F metal-web joist floors top-hung on the ICF, the UB under the set-back wall and the stairs (by others). [NRM2 16 / 22 / package FLR / JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		1	1	1	1	1	1	1	7						
4A	**1F and 2F floors - metal-web joists top-hung on the ICF (NRM2 16 - package FLR; floor designer / engineer)**															
	As modelled (rc_dress): 22 deck on 253 metal-web joists @ 600 spanning party to party (short span), top-hung on 47 x 225 C24 ledgers fixed to the ICF inner faces (ledger fixings into the core by the engineer); stair well 1,000 x 2,490 trimmed with doubled trimming joists + a 2/47 trimmer. The 2F floor stops at the set-back wall (rooms) - the balcony beyond is a warm deck (Bill 7). A 254 x 146 UB carries the set-back wall (engineer).															
4A.1	1F floor deck, 22 P5 T&G chipboard glued and screwed, net of the stair well	m2	810.46	369.25	471.07	233.49	572.88	131.67	471.07	**3,059.89**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,365.9
4A.2	2F floor deck to the set-back wall, 22 P5 T&G chipboard, net of the stair well	m2	706.74	321.97	410.76	203.58	499.56	114.79	410.76	**2,668.16**			£0.00	£0.00	**£0.00**	Order guide +10% = 2,935.0
4A.3	Metal-web joists 253 deep @ 600, top-hung on the ledgers (1F + 2F), ~3.6 m long	nr	768.00	352.00	448.00	224.00	544.00	128.00	448.00	**2,912.00**			£0.00	£0.00	**£0.00**	9,917.6 m in total
4A.4	47 x 225 C24 ledgers on the ICF inner faces (both party / gable sides, 1F + 2F), fixings through the EPS into the core	m	921.72	422.45	537.67	268.83	652.88	153.62	537.67	**3,494.84**			£0.00	£0.00	**£0.00**	Fixing design by the engineer - outside the ICF package
4A.5	Stair-well trimming: doubled trimming joists + 2/47 trimmer, hangers (1F + 2F)	m	826.56	377.00	480.74	238.67	584.49	134.92	480.74	**3,123.13**			£0.00	£0.00	**£0.00**	
4A.6	254 x 146 UB under the 2F set-back wall, bearing on the party / gable ICF (padstones / bearings in the core)	m	90.64	41.31	52.69	26.13	64.08	14.75	52.69	**342.30**			£0.00	£0.00	**£0.00**	Engineer to design - incl. 2 bearings per house
4A.7	Acoustic quilt 100 between the joists (Approved Document E internal floors, 40 dB) + resilient ceiling detail	m2	1,517.20	691.22	881.83	437.07	1,072.44	246.46	881.83	**5,728.05**			£0.00	£0.00	**£0.00**	Order guide +10% = 6,300.9
4A.8	Fire-stopping / airtightness seal at the floor zone against the ICF inner faces (1F + 2F perimeters)	m	1,284.26	587.70	748.44	373.37	909.19	212.63	748.44	**4,864.03**			£0.00	£0.00	**£0.00**	
4B	**Stairs (NRM2 22 - package JOI; stair manufacturer)**															
	Two straight stacked flights per house beside the party / gable wall: 14 risers 195.9 / 13 goings 230 (Part K), 900 wide, first riser 1,200 behind the front inner face. 3 storeys with a floor above 4.5 m: the stair must be a protected stairway (ADB Vol 1) - see Bill 9.															
4B.1	Softwood straight flight, 14 risers, 900 wide, strings, treads / risers, handrail, newels, fixings	nr	48.00	22.00	28.00	14.00	34.00	8.00	28.00	**182.00**			£0.00	£0.00	**£0.00**	GF-1F and 1F-2F
4B.2	2F landing balustrade round the stair well (900 high, Part K), newel + handrail	m	84.72	38.83	49.42	24.71	60.01	14.12	49.42	**321.23**			£0.00	£0.00	**£0.00**	

PACKAGE SUMMARY - Bill 4 Floors & Stairs - Metal-Web Joist Floors, Ledgers, Steel, Stairs (package FLR / JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
4A	1F and 2F floors - metal-web joists top-hung on the ICF (NRM2 16 - package FLR; floor designer / engineer)	£0.00	£0.00	**£0.00**
4B	Stairs (NRM2 22 - package JOI; stair manufacturer)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 4, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 5 - Roof Structure - Fink Trusses, Plates, Bracing, Fire-Stopping, Loft Insulation

Trussed roof per house from the front wall to the 2F set-back wall (by others; truss designer). [NRM2 16 / package RFS]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
5A	**Roof structure - trussed roof (NRM2 16 - package RFS; truss designer / engineer)**															
	One duo-pitch roof per house (party bay): Fink trusses C24 @ 600, 35 deg, span 8.61 m from the front wall to the set-back wall on 47 x 150 C24 wall plates on the ICF cores (plate top 8,276), overhang 307 each side, ridge ~11,618. The party walls run up under the roof (top of rafter - 50) and the blocks step a course at 12 party lines. Sizes, bracing and connections by the truss designer.															
5A.1	Fink trusses C24, 35 deg, span ~8.61 m, @ 600	nr	168.00	77.00	98.00	49.00	119.00	28.00	98.00	**637.00**			£0.00	£0.00	**£0.00**	7 per house (rc_dress set-out)
5A.2	47 x 150 C24 wall plates bedded on the front and set-back ICF walls, anchored into the core	m	181.27	82.62	105.39	52.27	128.15	29.50	105.39	**684.60**			£0.00	£0.00	**£0.00**	Order guide +10% = 753.1
5A.3	Truss clips / framing anchors, trusses to the plates	nr	336.00	154.00	196.00	98.00	238.00	56.00	196.00	**1,274.00**			£0.00	£0.00	**£0.00**	
5A.4	Restraint straps: plates to the ICF at 2 m, gable restraint straps at the block ends	nr	104.00	52.00	64.00	36.00	76.00	24.00	64.00	**420.00**			£0.00	£0.00	**£0.00**	Estimate - truss designer
5A.5	Longitudinal binders + diagonal rafter bracing 25 x 100 C24 (per BS 5268-3 / truss designer)	m	605.96	276.79	352.75	175.51	428.72	99.55	352.75	**2,292.04**			£0.00	£0.00	**£0.00**	Estimate
5A.6	Fire-stopping at the party-wall heads under the roof covering (mineral wool, Approved Document B)	m	247.43	107.58	139.85	64.55	172.13	32.27	139.85	**903.67**			£0.00	£0.00	**£0.00**	Along the raked party wall top, front face to set-back face
5A.7	Loft insulation 300 mineral wool (100 between + 200 cross-laid) over the 2F ceiling	m2	734.27	334.67	426.89	211.72	519.10	119.51	426.89	**2,773.03**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,050.3
5A.8	Eaves ventilation / rafter trays keeping the airway over the insulation (both eaves)	m	197.14	91.06	115.54	58.42	140.02	33.94	115.54	**751.69**			£0.00	£0.00	**£0.00**	

PACKAGE SUMMARY - Bill 5 Roof Structure - Fink Trusses, Plates, Bracing, Fire-Stopping, Loft Insulation (package RFS; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
5A	Roof structure - trussed roof (NRM2 16 - package RFS; truss designer / engineer)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 5, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 6 - Roof Coverings & Rainwater - Natural Slate, Eaves, Verges, Step Abutments, Gutters, PV

Slate coverings, eaves, verges, lead work at the roof steps, rainwater goods and PV (by others). [NRM2 18 / 33 / package RFC]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
6A Roof coverings, eaves, verges and abutments (NRM2 18 - package RFC)																
	Slope area = covering width (house width, + 326 verge past a block-end gable) x 2 slopes x 4.788 m plan run (incl. the 382 tile overhang) / cos 35. Natural slate + PV per the design and access ISO. Roof steps: lead soakers and stepped flashings where the higher roof meets the party-wall upstand.															
6A.1	Natural slate 500 x 250 on 25 x 50 treated battens and breathable underlay, nailed / hooked per BS 5534	m2	1,152.37	532.30	675.39	341.51	818.48	198.41	675.39	**4,393.85**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,833.2; plan 3,599.2 m2
6A.2	*25 x 50 treated battens at ~200 gauge*	*m*	*5,761.84*	*2,661.49*	*3,376.95*	*1,707.53*	*4,092.42*	*992.07*	*3,376.95*	*21,969.26*					*not priced*	*Guide - included in 6A.1*
6A.3	Ridge - dry-fix ventilated ridge system	m	98.57	45.53	57.77	29.21	70.01	16.97	57.77	**375.84**			£0.00	£0.00	**£0.00**	Order guide +10% = 413.4
6A.4	Dry verge / undercloak at the block-end gables	m	23.38	23.38	23.38	23.38	23.38	23.38	23.38	**163.67**			£0.00	£0.00	**£0.00**	Order guide +10% = 180.0
6A.5	Eaves: fascia, ventilated soffit, eaves carrier / tray, insect mesh (front eaves + set-back eaves over the balcony)	m	197.14	91.06	115.54	58.42	140.02	33.94	115.54	**751.69**			£0.00	£0.00	**£0.00**	Order guide +10% = 826.9
6A.6	Roof step abutments: Code 4 lead soakers + stepped cover flashings to the party-wall upstand (both slopes)	m	43.03	10.76	10.76	10.76	21.52		32.27	**129.10**			£0.00	£0.00	**£0.00**	Per step line: both slopes front face to set-back face
6B Rainwater goods (NRM2 33 - package RFC)																
6B.1	Gutters 112 half-round (uPVC / aluminium), brackets, outlets, stop ends - front eaves and set-back eaves	m	197.14	91.06	115.54	58.42	140.02	33.94	115.54	**751.69**			£0.00	£0.00	**£0.00**	Order guide +10% = 826.9
6B.2	Downpipes 68, clipped to the walls with swan necks at the eaves (fixings into the ICF webs) - 1 front + 1 rear per house	nr	48.00	22.00	28.00	14.00	34.00	8.00	28.00	**182.00**			£0.00	£0.00	**£0.00**	~1,534 m in total; the rear pipe passes the balcony - route to the designer
6C Solar PV (NRM2 - package M&E; PROVISIONAL)																
6C.1	Solar PV array per house (in-roof or on-roof, flashing kit, inverter, AC / DC cabling, isolators) - size to SAP / Part L	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - shown on the design and access ISO

PACKAGE SUMMARY - Bill 6 Roof Coverings & Rainwater - Natural Slate, Eaves, Verges, Step Abutments, Gutters, PV (package RFC; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
6A	Roof coverings, eaves, verges and abutments (NRM2 18 - package RFC)	£0.00	£0.00	**£0.00**
6B	Rainwater goods (NRM2 33 - package RFC)	£0.00	£0.00	**£0.00**
6C	Solar PV (NRM2 - package M&E; PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 6, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 7 - Balcony - Warm Deck, Waterproofing, Paving, Copings, Balustrade

Rear second-floor balcony per house: everything except the ICF parapet and fins (by others). [NRM2 18 / 22 / package BAL]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
7A	**Rear 2F balcony behind the 1,500 set-back (NRM2 18 / 22 - package BAL; designer)**															
	Per house: deck 1,144 deep (set-back outer face to the parapet inner face) x the inner width, over the 1F rooms (warm deck). The ICF provides the 2-course (914) 6in XR35 parapet on the rear face and the raked party / gable fins; deck, waterproofing, drainage, copings and the 1,100 railing are by others.															
7A.1	Warm-deck roof over the 1F rooms: VCL, PIR to falls, waterproofing membrane (single-ply / liquid), to Part L / C	m2	103.72	47.28	60.30	29.91	73.33	16.88	60.30	**391.73**			£0.00	£0.00	**£0.00**	Order guide +10% = 430.9
7A.2	Balcony finish: porcelain / concrete paving on adjustable pedestals over the membrane	m2	103.72	47.28	60.30	29.91	73.33	16.88	60.30	**391.73**			£0.00	£0.00	**£0.00**	Order guide +10% = 430.9
7A.3	Membrane upstands (150 min above the finished deck) to the set-back wall, fins and parapet, termination bars	m	236.20	107.80	137.43	68.29	167.06	38.66	137.43	**892.88**			£0.00	£0.00	**£0.00**	Order guide +10% = 982.2
7A.4	Balcony rainwater outlet + overflow spout through the parapet, connected to the rear downpipe	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	
7A.5	Level-threshold drainage channel at the balcony door	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	
7A.6	Parapet coping on the 2-course rear ICF parapet (with DPC, drips, fixings into the core)	m	97.92	44.88	57.12	28.56	69.36	16.32	57.12	**371.28**			£0.00	£0.00	**£0.00**	Order guide +10% = 408.4
7A.7	Raked coping on the party / gable fins (set-back eaves to the parapet top)	m	56.26	27.00	33.76	18.00	40.51	11.25	33.76	**220.53**			£0.00	£0.00	**£0.00**	Order guide +10% = 242.6
7A.8	Balustrade to 1,100 above the deck on the parapet (glass or metal, Part K), fixed through the coping into the ICF core	m	90.64	41.31	52.69	26.13	64.08	14.75	52.69	**342.30**			£0.00	£0.00	**£0.00**	

PACKAGE SUMMARY - Bill 7 Balcony - Warm Deck, Waterproofing, Paving, Copings, Balustrade (package BAL; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
7A	Rear 2F balcony behind the 1,500 set-back (NRM2 18 / 22 - package BAL; designer)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 7, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 8 - Internal Linings - ICF and Party Wall Faces, Ceilings, Reveals

Dry linings to the inside faces of the external ICF walls and the party walls, ceilings, reveals and stair soffits (partition linings in Bill 9). [NRM2 28 / package DRY]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		1	1	1	1	1	1	1	7						
8A	**Wall linings (NRM2 28 - package DRY)**															
	Measured on the ICF inner faces per storey (no internal layout designed - partitions in Bill 9): GF 0 to the u/s of the 1F joists 2,468; 1F 2,468; 2F to the u/s of the truss chords 2,790 (2F depth front wall to set-back wall). External openings deducted at their storey. Board types are proposals - mechanical fixings into the ICF webs.															
8A.1	GF external walls (ICF inner face): 12.5 wallboard on dabs + mechanical fixings to the webs (MR in wet rooms)	m2	311.42	167.27	200.54	122.92	233.80	89.65	200.54	**1,326.13**			£0.00	£0.00	**£0.00**	Order guide +10% = 1,458.7
8A.2	1F external walls (ICF inner face): 12.5 wallboard on dabs + mechanical fixings to the webs (MR in wet rooms)	m2	348.88	184.44	222.38	133.84	260.33	95.89	222.38	**1,468.14**			£0.00	£0.00	**£0.00**	Order guide +10% = 1,615.0
8A.3	2F external walls (ICF inner face): 12.5 wallboard on dabs + mechanical fixings to the webs (MR in wet rooms)	m2	412.70	212.35	258.59	150.71	304.82	104.48	258.59	**1,702.23**			£0.00	£0.00	**£0.00**	Order guide +10% = 1,872.5
8A.4	GF party walls (6in Standard ICF), each house side: 15 sound / fire board on dabs per the separating-wall detail	m2	1,090.09	473.95	616.14	284.37	758.33	142.19	616.14	**3,981.21**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,379.3; robust detail / pre-completion testing
8A.5	1F party walls (6in Standard ICF), each house side: 15 sound / fire board on dabs per the separating-wall detail	m2	1,090.09	473.95	616.14	284.37	758.33	142.19	616.14	**3,981.21**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,379.3; robust detail / pre-completion testing
8A.6	2F party walls (6in Standard ICF), each house side: 15 sound / fire board on dabs per the separating-wall detail	m2	1,039.71	452.05	587.66	271.23	723.28	135.61	587.66	**3,797.19**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,176.9; robust detail / pre-completion testing
8A.7	Internal reveals to windows and doors, 212 deep: 12.5 board / bonding and skim	m2	237.06	108.65	138.29	69.14	167.92	39.51	138.29	**898.86**			£0.00	£0.00	**£0.00**	Order guide +10% = 988.7
8B	**Ceilings (NRM2 28 - package DRY)**															
8B.1	GF ceilings, u/s 1F joists: 15 board (fire / acoustic per the floor detail), stair well deducted	m2	810.46	369.25	471.07	233.49	572.88	131.67	471.07	**3,059.89**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,365.9
8B.2	1F ceilings, u/s 2F joists: 15 board, stair well deducted	m2	810.46	369.25	471.07	233.49	572.88	131.67	471.07	**3,059.89**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,365.9
8B.3	2F ceilings under the truss chords: 12.5 board + 500g VCL (taped, sealed at the ICF)	m2	734.27	334.67	426.89	211.72	519.10	119.51	426.89	**2,773.03**			£0.00	£0.00	**£0.00**	Order guide +10% = 3,050.3
8B.4	Stair soffit linings, sloping (2 flights per house)	m2	169.69	77.77	98.98	49.49	120.20	28.28	98.98	**643.40**			£0.00	£0.00	**£0.00**	
8C	**Jointing, beads and skim (NRM2 28 - package DRY)**															
8C.1	Scrim tape to board joints (walls / 1.2 m; ceilings / 1.2 + 2.4 m)	m	6,931.05	3,165.90	4,034.78	2,007.39	4,903.66	1,138.51	4,034.78	**26,216.06**			£0.00	£0.00	**£0.00**	Order guide +10% = 28,837.7
8C.2	Scrim tape to internal angles (room corners on the ICF faces, wall to ceiling)	m	2,596.13	1,188.51	1,513.34	755.40	1,838.18	430.56	1,513.34	**9,835.45**			£0.00	£0.00	**£0.00**	Order guide +10% = 10,819.0
8C.3	Angle beads to window and door reveals (jambs and heads)	m	1,120.86	513.73	653.83	326.92	793.94	186.81	653.83	**4,249.92**			£0.00	£0.00	**£0.00**	Order guide +10% = 4,674.9
8C.4	Skim coat 2-3 to all board faces measured in 8A / 8B	m2	7,054.82	3,223.61	4,107.73	2,044.77	4,991.86	1,160.65	4,107.73	**26,691.18**			£0.00	£0.00	**£0.00**	Face layer only

PACKAGE SUMMARY - Bill 8 Internal Linings - ICF and Party Wall Faces, Ceilings, Reveals (package DRY; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
8A	Wall linings (NRM2 28 - package DRY)	£0.00	£0.00	**£0.00**
8B	Ceilings (NRM2 28 - package DRY)	£0.00	£0.00	**£0.00**
8C	Jointing, beads and skim (NRM2 28 - package DRY)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 8, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 9 - Internal Fit-Out - Partitions, Doors, Joinery, Kitchens, Sanitaryware (PROVISIONAL per dwelling)

Per-dwelling provisional allowances where no internal layout exists yet, plus the measured window boards and loft hatches. [NRM2 16 / 22 / 24 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
9A	**Internal layout - PROVISIONAL per dwelling (NRM2 16 / 24 / 22 - package JOI; layout NOT designed)**															
	Outline consent: no floor plans. The rates below are PER DWELLING allowances for a 3-bed 5-person 3-storey terraced house (~99.6 m2 GIA: GF kitchen / living + WC, 1F living / bedroom 1 + bathroom, 2F bedrooms 2 and 3) - replace with measured quantities when the internal layout is designed. 3 storeys (a floor above 4.5 m): protected stairway - FD20 self-closing doors to the habitable rooms off the stair (ADB Vol 1) unless an alternative (sprinklers / open-plan strategy) is adopted.															
9A.1	Timber stud partitions 38 x 89 C16 @ 600 + 15 board both faces, incl. linings, insulation to bathroom / WC walls, pattresses	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.2	Internal doorsets (approx. 8 per house) incl. FD20 self-closing doors on the protected stair, linings, stops	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.3	Ironmongery: hinges, latches, privacy sets (bathroom / WC), door closers to FD20 doors, stops	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.4	Skirtings and architraves (MDF / softwood), all rooms	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.5	Kitchen units, worktops and appliances	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.6	Sanitaryware: bathroom + GF WC (WC, basin, bath / shower), taps, wastes	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9A.7	Floor finishes (carpet / vinyl / LVT) and decorations (mist + 2 coats, woodwork)	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
9B	**Second-fix joinery measured from the model (NRM2 22 - package JOI)**															
	Window boards: length = SO width + 2 x 50 horns; depth = internal reveal 212 + 25 nosing = 237 (order 250 MDF / uPVC).															
9B.1	Window board 250 x 1,300 long, with horns and nosing	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	
9B.2	Window board 250 x 1,150 long, with horns and nosing	nr	168.00	77.00	98.00	49.00	119.00	28.00	98.00	**637.00**			£0.00	£0.00	**£0.00**	
9B.T	**Window boards - total length**	**m**	**224.40**	**102.85**	**130.90**	**65.45**	**158.95**	**37.40**	**130.90**	**850.85**					*not priced*	**Order guide +10% = 935.9**
9B.3	Loft access hatch in the 2F ceiling, insulated and draught-sealed, between the trusses (trimming by the truss designer)	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	One per dwelling

PACKAGE SUMMARY - Bill 9 Internal Fit-Out - Partitions, Doors, Joinery, Kitchens, Sanitaryware (PROVISIONAL per dwelling) (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
9A	Internal layout - PROVISIONAL per dwelling (NRM2 16 / 24 / 22 - package JOI; layout NOT designed)	£0.00	£0.00	**£0.00**
9B	Second-fix joinery measured from the model (NRM2 22 - package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 9, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 10 - Services - Electrical & Mechanical (PROVISIONAL per dwelling)

Mechanical and electrical services as per-dwelling allowances (no design yet); ICF sleeves before the pour. [NRM2 38-40 / package M&E]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
10A	**Mechanical and electrical services - PROVISIONAL per dwelling (NRM2 38 / 39 / 40 - package M&E; M&E designer)**															
	No services design exists. Per-dwelling allowances to be replaced by the M&E designer's quantities. All penetrations through the ICF (incoming services, soil / waste, ventilation, flues) are SLEEVED BEFORE THE POUR - positions must reach BuildEase before the pre-cut kit is released.															
10A.1	Electrical installation: consumer unit, circuits, accessories, lighting, LD2 smoke / heat alarms (3 storeys), TV / data	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
10A.2	EV charge point (Approved Document S) where parking is provided	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling with parking
10A.3	Heating and hot water: air-source heat pump, cylinder, emitters, controls (Part L 2021 / Future Homes)	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
10A.4	Ventilation to Part F: dMEV / MVHR, ducting, terminals through the ICF	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
10A.5	Hot and cold water, soil and waste (above ground), incoming water main	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - per dwelling
10A.6	Sleeves through the ICF for the service entries / terminals, cast in before the pour (approx. 6 per house)	nr	144.00	66.00	84.00	42.00	102.00	24.00	84.00	**546.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - positions to BuildEase
10A.7	Builder's work in connection with services (chases in the EPS, fire-stopping round penetrations) - per block	item	1.00	1.00	1.00	1.00	1.00	1.00	1.00	**7.00**			£0.00	£0.00	**£0.00**	PROVISIONAL

PACKAGE SUMMARY - Bill 10 Services - Electrical & Mechanical (PROVISIONAL per dwelling) (package M&E; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
10A	Mechanical and electrical services - PROVISIONAL per dwelling (NRM2 38 / 39 / 40 - package M&E; M&E designer)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 10, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 11 - Design, Approvals, Surveys & Certification

Consultants, surveys, approvals and certification still outstanding on an outline-consent site (by the client). [- / package DES]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Description	Unit	Block D 24 houses	Block E 11 houses	Block F 14 houses	Block G 7 houses	Block H 17 houses	Block I 4 houses	Block J 14 houses	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
																Blocks: D = 24 houses D01-D24; E = 11 houses E01-E11; F = 14 houses F01-F14; G = 7 houses G01-G07; H = 17 houses H01-H17; I = 4 houses I01-I04; J = 14 houses J01-J14
	One column per block (multiplier 1) - Site total = SUMPRODUCT of the multipliers and th		**1**	**1**	**1**	**1**	**1**	**1**	**1**	**7**						
11A	**Design, approvals, surveys and certification (package DES; by the client / their consultants)**															
	Outline consent only - the detailed design is outstanding. Pre-completion sound testing (Approved Document E) and air-tightness testing (Part L) are already in the ICF BOQ preliminaries (items A.14 / A.15) and are not repeated here.															
11A.1	Reserved matters / detailed planning: house-type plans and elevations, materials, levels (architect)	item											£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Lump sum
11A.2	Topographic survey and proposed site levels / external works and drainage design (incl. the cross-fall regrade)	item											£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Lump sum
11A.3	Site investigation incl. radon / ground-gas assessment and foundation recommendations	item											£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Lump sum
11A.4	Structural engineer: strip footings and steps, floors and ledgers on the ICF, UB under the set-back wall, roof, ICF checks - per block	item	1.00	1.00	1.00	1.00	1.00	1.00	1.00	**7.00**			£0.00	£0.00	**£0.00**	Per block
11A.5	Fire strategy for the 3-storey houses (protected stairway / alternative, ADB Vol 1)	item											£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Lump sum
11A.6	Building control (LABC / approved inspector) - per dwelling	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	
11A.7	Structural warranty (LABC Warranty / NHBC / Premier) - per dwelling; ICF 3-storey acceptance to be confirmed	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	
11A.8	SAP / EPC, Part L / O (overheating) and Part G water calculations - per dwelling	nr	24.00	11.00	14.00	7.00	17.00	4.00	14.00	**91.00**			£0.00	£0.00	**£0.00**	

PACKAGE SUMMARY - Bill 11 Design, Approvals, Surveys & Certification (package DES; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
11A	Design, approvals, surveys and certification (package DES; by the client / their consultants)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 11, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Schedule A - Areas per House (end house and mid-terrace house)

Per dwelling, from the house frame of the model (rc_dress) and the spec openings. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

House	Item	m2
end house (gable)	GF slab inside the ICF (gross)	34.39
end house (gable)	1F floor (net of the well)	31.90
end house (gable)	2F floor to the set-back wall (net of the well)	27.80
end house (gable)	Balcony deck	4.10
end house (gable)	Roof covering on the slope	51.51
end house (gable)	2F ceiling (loft insulation)	29.01
end house (gable)	External finish - Front (net)	24.63
end house (gable)	External finish - Rear (GF / 1F + balcony parapet) (net)	20.01
end house (gable)	External finish - Set-back wall (2F, balcony) (net)	6.62
end house (gable)	External finish - Gable (net)	99.04
end house (gable)	External finish - Balcony fins + parapet (inner faces above the deck) (net)	7.59
end house (gable)	Wall linings GF - ICF external / party	57.43
end house (gable)	Wall linings 1F - ICF external / party	58.99
end house (gable)	Wall linings 2F - ICF external / party	59.43
mid-terrace house	GF slab inside the ICF (gross)	36.43
mid-terrace house	1F floor (net of the well)	33.94
mid-terrace house	2F floor to the set-back wall (net of the well)	29.60
mid-terrace house	Balcony deck	4.34
mid-terrace house	Roof covering on the slope	47.70
mid-terrace house	2F ceiling (loft insulation)	30.74
mid-terrace house	External finish - Front (net)	24.63
mid-terrace house	External finish - Rear (GF / 1F + balcony parapet) (net)	20.01
mid-terrace house	External finish - Set-back wall (2F, balcony) (net)	7.21
mid-terrace house	External finish - Balcony fins + parapet (inner faces above the deck) (net)	7.78
mid-terrace house	Wall linings GF - ICF external / party	58.48
mid-terrace house	Wall linings 1F - ICF external / party	60.04
mid-terrace house	Wall linings 2F - ICF external / party	60.62

End houses lose the party-wall half-thickness on the gable side (inner width 3,581.5 vs 3,794.3) and gain the gable and its verge.

Schedule B - Opening Schedule per House (11 openings, every house)

From RC_spec_B<k>.json (1001 openings site-wide = 91 x 11). Sill / head above the house FFL. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Ref	Level	Face	Type	W mm	H mm	Sill mm	Head mm	Room / note	Site nr
D1	GF	front	door	1010	2134	0	2134	front door 1,010 SO (composite, level threshold)	91
W1	GF	front	window	1200	1372	762	2134	GF front window (kitchen)	91
D2	GF	rear	door	1800	2134	0	2134	GF rear patio doors 1,800 SO	91
W2	1F	front	window	1050	1524	762	2286	1F front (living)	91
W3	1F	front	window	1050	1524	762	2286	1F front (living)	91
W6	1F	rear	window	1050	1372	762	2134	1F rear (bed 1)	91
W7	1F	rear	window	1050	1372	762	2134	1F rear (bath)	91
W4	2F	front	window	1050	1219	914	2134	2F front (bed 2)	91
W5	2F	front	window	1050	1219	914	2134	2F front (bed 3)	91
D3	2F	set-back (balcony)	door	900	2134	0	2134	2F balcony door 900 SO (level threshold onto the balcony deck)	91
W8	2F	set-back (balcony)	window	1050	1219	914	2134	2F rear (bed 2/3)	91

Mirrored handing alternates per house (spec slots). Front faces / rear faces per block: see Schedule D.

Schedule C - Key Quantities per Block

Reference only - the bills carry the priced quantities. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Block	Houses	Plots	Step lines	External finish m2	Roof slope m2	Floors 1F+2F m2	GF slab m2	Openings nr
Block D	24	D01-D24	4	1,627.44	1,152.37	1,517.19	870.22	264.00
Block E	11	E01-E11	1	852.36	532.30	691.22	396.64	121.00
Block F	14	F01-F14	1	1,031.23	675.39	881.83	505.93	154.00
Block G	7	G01-G07	1	613.88	341.51	437.07	250.92	77.00
Block H	17	H01-H17	2	1,210.09	818.48	1,072.44	615.21	187.00
Block I	4	I01-I04	0	435.01	198.41	246.46	141.63	44.00
Block J	14	J01-J14	3	1,031.23	675.39	881.83	505.93	154.00
Total	**91.00**		**12.00**	**6,801.24**	**4,393.85**	**5,728.04**	**3,286.48**	**1,001.00**

External finish = net of openings on the ICF outer face incl. the balcony faces.

Schedule D - Levels, Steps and Exposure at DPC per Block (provisional)

EA LiDAR existing ground along both long faces of every plot (RC_levels.json); FFL = pair mean ground + 150, whole-course steps. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation models (one model per block) of the house type we designed on the outline consent; no allowance for waste is included unless stated. Quantity columns are the 7 blocks D to J; the Site total is their sum. Items marked PROVISIONAL are allowances per dwelling where no design exists yet. Rates and amounts are by others.

Block	Houses	Ground m AOD	Fall along m	Cross-fall m	Long faces	Datum FFL m AOD	Step lines	Step courses per house (U1..)	ICF exposed below DPC m2	Ground above DPC m2
Block D	24	62.43 - 64.46	2.03	0.26	SE / NW	62.64	4	0 0 0 0 0 0 1 1 2 2 3 3 3 3 3 3 3 3 4 4 4 4 4 4	14.63	24.79
Block E	11	63.84 - 64.29	0.29	0.53	E / W	64.04	1	1 1 1 1 1 1 1 1 1 0 0	24.20	6.26
Block F	14	66.83 - 67.18	0.19	0.57	N / S	66.99	1	0 0 0 0 1 1 1 1 1 1 1 1 1 1	28.53	10.41
Block G	7	64.34 - 64.94	0.51	0.33	E / W	64.63	1	0 0 0 0 0 0 1	4.97	5.85
Block H	17	63.07 - 64.20	1.04	-0.24	SE / NW	63.32	2	0 0 1 1 1 1 2 2 2 2 2 2 2 2 2 2 2	5.31	13.43
Block I	4	63.91 - 64.14	0.23	0.17	SE / NW	64.09	0	0 0 0 0	0.94	4.00
Block J	14	64.48 - 65.78	1.30	-0.72	S / N	64.69	3	0 0 1 1 2 2 2 2 2 2 2 2 3 3	24.08	17.05

Cross-fall = face A minus face B. Exposure / cut are on EXISTING ground - the regrade (by others) changes both.