PRICE SCOPE: only the Nudura ICF formwork and associated accessories are included in our price.
All other structure and information shown is supplied in good faith for coordination only and must be checked by the relevant professional.

QUOTATION - NOT FOR CONSTRUCTION



SITE PLAN

Scale 1:750 @ A3 | 2261 P1 base (architect, outline), ICF blocks in red

ICF block (external face); heavy edge = FRONT

Step party wall (FFL steps 457.2)

Party wall, no step

D01 63.101 = plot id + GF FFL (m AOD)

0 10 20 30 40 m

BLOCK SCHEDULE

BLOCKS

Block	Houses	Plots	Fr/Rear	Steps	GF FFL AOD	Ground AOD
D	24	D01-D24	SE/NW	4	62.644-64.473	62.43-64.46
E	11	E01-E11	W/E	1	64.040-64.497	63.84-64.29
F	14	F01-F14	N/S	1	66.990-67.447	66.83-67.18
G	7	G01-G07	E/W	1	64.630-65.087	64.34-64.94
H	17	H01-H17	SE/NW	2	63.324-64.238	63.07-64.20
I	4	I01-I04	SE/NW	0	64.090-64.090	63.91-64.14
J	14	J01-J14	S/N	3	64.691-66.063	64.48-65.78
Total	**91**			**12**		

Fr/Rear = the faces' compass direction. Ground = LiDAR existing ground, mean of the front + rear faces per plot (m). Steps = party walls with a one-course (457.2) step.

GF FLOOR LEVELS PER RUN

Block	Plots	No.	FFL AOD	Above datum	Ground AOD
D	D01-D06	6	62.644	+0	62.43-62.69
D	D07-D08	2	63.101	+457	62.98-63.32
D	D09-D10	2	63.558	+914	63.51-63.63
D	D11-D18	8	64.016	+1,372	63.69-64.07
D	D19-D24	6	64.473	+1,829	64.16-64.46
E	E01-E09	9	64.497	+457	63.87-64.29
E	E10-E11	2	64.040	+0	63.84-63.94
F	F01-F04	4	66.990	+0	66.83-67.15
F	F05-F14	10	67.447	+457	66.83-67.18
G	G01-G06	6	64.630	+0	64.34-64.77
G	G07	1	65.087	+457	64.94-64.94
H	H01-H02	2	63.324	+0	63.07-63.28
H	H03-H06	4	63.781	+457	63.46-63.92
H	H07-H17	11	64.238	+914	64.08-64.20
I	I01-I04	4	64.090	+0	63.91-64.14
J	J01-J02	2	64.691	+0	64.48-64.60
J	J03-J04	2	65.148	+457	64.93-65.06
J	J05-J12	8	65.605	+914	65.16-65.57
J	J13-J14	2	66.063	+1,372	65.67-65.78

Run = houses at one FFL between steps. Above datum = the run's raise over the block's lowest FFL (whole 457.2 courses).

NOTES

1. Base: Franklin Ellis drawing WRQ-FEA-S1-00-DP-A-2261 P1 Illustrative Site Proposed B1 (outline planning), reproduced for location only. Block footprints in red = the Nudura ICF quotation block models (external wall faces, 4,080 x 10,312 per house) placed on the front edge of the 2261 block outlines (the outlines also take the rear outrigger zone, excluded).
2. Plot ids: block letter + house number counted left to right seen from the FRONT (= model units U1..Un); the architect's plot numbering is not issued - to be cross-referenced.
3. GF FFL per plot (m AOD): no proposed levels at outline. FFL per pair of houses = mean existing ground (EA LiDAR DTM 1 m) + 150, stepped in whole courses (457.2) at the party walls - 12 steps on the site. Front-to-back cross-falls regraded by others. Levels for the engineer / architect to confirm.
4. Stepped footing course: see ES26-064-FD-01. Do not scale; setting out by others.

REVISIONS

REV	DATE	DESCRIPTION

Nudura™ BuildEase

CLIENT	PROJECT
Cuckfield Real Estate Ltd	Redcatch Quarter, Knowle, Bristol

DRAWING TITLE

SITE PLAN - BLOCKS, PLOTS AND FLOOR LEVELS

2261 site plan with the ICF blocks, plot ids and stepped FFLs

SCALE	SIZE	DATE
1:750	A3	10.11.26
DRAWN	CHECKED	APPROVED
TS		

STATUS	DRAWING No.	REV
QUOTATION	ES26-064-SP-01	

Do not scale. All dimensions in mm. Check all dimensions on site.